

| 10x20-RIWF Run In Wood Foundation Materials - Build Your Own Horse Barn iCreatables.com | | | |
|--|---|----------------------|-------------|
| EXTERIOR MATERIALS | | | |
| CODE | DESCRIPTION | LENGTH / SIZE | QTY. |
| W7 | T1-11 sheet siding, or similar | 4x8x1/2 | 15 |
| T4 | 1x4 Trim | 16'-0" | 10 |
| T2 | 1x2 Pine Battens | 10'-0" | 68 |
| R5 | Metal drip edge | 1-1/2"x1-1/2" "x10' | 8 |
| R6 | 15 lb. roofing felt | 1 roll | 254 + sf. |
| R7 | 25 year asphalt shingles | 2.6 squares | 254 sf |
| S1 | Tow Straps | see plans | 4 |
| FOUNDATION MATERIALS | | | |
| CODE | DESCRIPTION | LENGTH / SIZE | QTY. |
| F3 | 6x6 Skid, treated | 10'-0" | 7 |
| F5 | Gravel under the wood skid foundation per owner | | |
| F10 | Simpson HL33, Rails attach to posts | | 4 |
| F12 | Simpson PS418, Rail Butt Joists | | 2 |
| WALL FRAMING MATERIALS | | | |
| CODE | DESCRIPTION | LENGTH / SIZE | QTY. |
| W1 | 4x4 Post | 8'-0" | 10 |
| W2 | 2x4 Girt boards | 10'-0" | 30 |
| W3 | LVL Header | 1 3/4" x 5 1/2"x20' | 4 |
| W5* | 2x6 Kick Boards | 16'-0" | 26 |
| PC3 | Simpson Post Cap | BC4 | 10 |
| | * 4x8 plywood or O.S.B. sheeting may be substituted for oak girt boards | | 7 |
| ROOF FRAMING MATERIALS | | | |
| CODE | DESCRIPTION | LENGTH / SIZE | QTY. |
| R1 | 2x4 Rafter Top Chord | 14'-0" | 13 |
| R1.1 | 2x4 Bottom Chord | 9'-0" | 11 |
| R2 | O.S.B. roof sheeting | 4'x8'x 7/16" | 10 |
| R4 | 2x6 Fascia | 12'-0" | 4 |
| R5 | O.S.B. Gusset Material | 4'x8'x 7/16" | 1 |
| R12 | 2x4 Blocking | 10'-0" | 4 |
| FASTENERS | | | |
| 8d 2-1/2" | Galvanized (Roof sheeting) | | 5 lbs |
| 12d 3 1/4" | Galvanized (Girt Boards) | | 5 lbs. |
| 8d 2-1/2" | Galvanized (Siding) | | 5 lbs. |
| | Metal Roof 1/4" hex head screw with neoprene bonded washer (Optional) | | 5 lbs. |
| | Asphalt Roof 1 1/4" long, 12 gauge, 3/8" head Roofing Nail | | 5 lbs. |
| Staples | Staples (batten attach) 1" 16 gauge, standard crown (1/2") (verify) | | 5 lbs. |
| | Lag Screw for HL33 brackets | 1/2" x 2" | 14 |