

24x22-RILT Run In Lean To shed Materials			
EXTERIOR MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W7	4x8 Textured Plywood	4'x8'x1/2"	21
T2	1x2 Pine Battens	9'	90
T4	1x4 Trim	8'	45
R5	Metal drip edge	1-1/2"x1-1/2" "x10'	12
R6	15 lb. roofing felt	2 rolls	600 + sf.
R7	25 year asphalt shingles	6 squares	600 sf
W7	Alternate Siding 1x10 Pine Boards	9'-0"	100
FOUNDATION MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F11	12" round con.c footing	12"	4
F12	18" round conc. footing	18"	11
WALL FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W1	4x4 Treated Post	12'-0"	5
W1.1	4x4 Treated Post	14'-0"	3
W1.2	4x4 Treated Post	10'-0"	6
W1.3	6x6 Treated Post	12'-0"	3
W2	2x4 Oak Girt boards	12'-0"	50
W3	1 3/4" x 7 1/4" LVL Beam	24'-0"	5
W5*	1x8 Oak Kick Boards	8'-0"	44
W6	2x12 Pine Board	12'-0"	4
W8	1 3/4" x 11 7/8" LVL Beam	24'-0"	2
PC1	Simpson Post Cap	EPC44	4
PC2	Simpson Post Cap	PC44	4
PC3	Simpson Post Cap	BC44	4
PC4	Simpson Post Cap	EPC66	2
PC5	Simpson Post Cap	PC66	1
PC6	Simpson Post Cap	AC6	8
*kick boards may be substituted with 3/4" plywood or O.S.B			
ROOF FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
R1	2x8 Rafter Top Chord	14'-0"	15
R1.1	2x8 Rafter Top Chord	12'-0"	15
R2	O.S.B. roof sheeting	4'x8'x 7/16"	20
R4	2x8 Facia	16'	4
R15	Simpson H2.5A tie		52