

8x16-H Hip Roof Shed Materials - Build Your Own Backyard Shed iCreatables.com

EXTERIOR MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W7	T1-11 Siding	4'x8'x 1/2"	11
T4	1x4 Trim	16'-0"	7
R5	Metal drip edge	1-1/2"x1-1/2" "x10'	6
R6	15 lb. roofing felt	173 sf.	
R7	25 year asphalt shingles	173 sf.	1.5 squares
FOUNDATION MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F3	4x6 Skid, treated	16'-0"	2
F5	Gravel. Site verify amount		
FLOOR FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F1	2x6 Floor Joist	8'-0"	13
F2	2x6 Rim Joist	16'-0"	2
F2.1	2x6 Rim Joist	10'-0"	1
F4	Full Face O.S.B. T.&G.	4'x8'x 3/4"	4
F10	SIMPSON A23 CLIP		10
WALL FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W1	2x4 Wall Stud Lumber	92 5/8"	36
W2	2x4 Wall Plate, short	8'-0"	6
W3	2x4 Wall Plate, long	16'-0"	6
W5	2x4 Door Trimmer	8'-0"	2
W6	2x6 Door Header	8'-0"	2
W7	4ft. x 8ft. Textured Plywood Siding, See exterior materials		
ROOF FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
R1	2x6 Truss Top Chord	8'-0"	10
R1-A	2x4 Truss Bottom Chord	8'-0"	5
R1-B	2x4 Truss Collar Beam	Use Scrap	
R1.2	2x6 Rafter	8'-0"	2
R1.3	2x6 Rafter	8'-0"	4
R1.4	2x6 Jack Rafter	16'-0"	2
R2	O.S.B. roof sheeting	4'x8'x 7/16"	7
R4	2x6 Fascia	20'-0"	3
R12	2x6 Blocking	16'-0"	3
R15	Simpson Hurricane Tie	H2.5	14
DOOR FRAMING MATERIALS - SEE DOOR FRAMING PLANS			
FASTENERS (see door plans for door fasteners)			
2 1/2"	8d Coated Sinker-Roof Sheet, Joist/Rafter to Wall		8 lbs
3 1/4"	12d Coated Sinker-Floor Joist, Wall Frame		10 lbs.
2 1/2"	8d Galvanized-Siding		10 lbs.
	Asphalt Roof 1 1/4" long, 12 gauge, 3/8" head Roofing Nail		5 lbs.
	Optional Trim Screws #9 flat head, polymer 2.5"		
	Construction Adhesive	10 oz.	6