

22x30-RITR-LT Run In Tack Room Truss Materials - Build Your Own Backyard Shed iCreatables.com

EXTERIOR MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W7	4x8 Textured Plywood Sheet	4x8x1/2"	36
T4	1x4 Trim	16'	24
T2	1x2 Pine Battens	10'	100
R5	Metal drip edge	1-1/2"x1-1/2" "x10'	12
R6	15 lb. roofing felt		2 740 + sf.
R7	25 year asphalt shingles	7.6 squares	740 sf
R16	Ridge Vent	30lf	1
FOUNDATION MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F12	12" Round Concrete Footings.		24
FLOOR FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F3	4x6 Skid, Treated	12'-0"	3
F4	2x8 Tongue and Groove Decking	12'-0"	10
WALL FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W1	4x4 Oak Post (rear wall bearing)	12'-0"	10
W1.1	6x6 Oak Post (center wall bearing)	10'-0"	10
W1.2	6x6 Post (front wall)	12'-0"	4
W2	2x4 Girt boards/Kick Board Support	12'-0"	56
W2.1	2x4 Door furr out	8'-0"	12
W3	1 3/4" x 7 1/4" LVL Beam	30'-0"	2
W5*	1x8 Oak Kick Boards	8'-0"	64
W6	2x6 Header	12'-0"	5
W8	1 3/4" x 9 1/4" LVL Beam	30'-0"	3
PC1	Simpson Post Cap	EPC44	4
PC2	Simpson Post Cap	PC44	6
PC3	Simpson Post Cap	BC44	6
PC4	Simpson Post Cap	EPC66	2
PC5	Simpson Post Cap	PC66	2
ROOF FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
R1	4/12 Engineered Common Truss	22'-0"	16
R2	O.S.B. roof sheeting	4'x8'x 1/2"	26
R4	2x6 Fascia	18'-0"	4
R4.1	2x6 Fascia	14'-0"	6
R4	2x4 Fascia	18'-0"	4
R4.1	2x4 Fascia	14'-0"	6
R8	Simpson H1 Hurricane Tie		32
FASTENERS			
2 1/2"	8d Coated Sinker-Roof Sheet, Rafter to Wall		15 lbs.
3 1/4"	12d Galvanized-Girt Boards		20 lbs.
2 1/2"	8d Galvanized-Siding		15 lbs.
	Metal Roof 1/4" hex head screw with neoprene bonded washer Optional		15 lbs.
	Asphalt Roof 1 1/4" long, 12 gauge, 3/8" head Roofing Nail		15 lbs.
10d	Simpson Hanger Nails 1 1/2" Galvanized	N10D5HDG	2 lbs.
Staples	Staples (batten attach) 1 1/4" 16 gauge, standard crown (1/2") (verify)		5 lbs.