

12x18-LT Lean To Shed Materials - Build Your Own Backyard Shed iCreatables.com			
EXTERIOR MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W7	T1-11 Siding	4'x8'x 1/2"	15
T4	1x4 Trim	3 1/4" x 10'	11
R5	Metal Drip Edge, install under roofing	1 1/2" x 1 1/2" x 10'	6
R5.1	Metal Drip Edge, install on top of roofing	4" x 4" x 10'	2
R6	15 lb. roofing felt		1 roll
R7	36" wide PBR metal roofing	36" x 13'-5"	6
*R7	Asphalt Roofing option (verify low slope application)	252 sf	2.6 squares
R11	Corrugated roofing closure strip	10lf.	4
W10	"Z" Metal flashing	10'-0"	4
FOUNDATION MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F3	4x6 Skid, treated	18'-0"	3
F5	Gravel		
FLOOR FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
F1	2x6 Floor Joist	12'-0"	15
F2	2x6 Rim Joist	18'-0"	2
F4	Full Face O.S.B. T.&G.	4'x8'x 3/4"	7
WALL FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
W1	2x4 Lumber	8'-0"	35
W1.5	2x4 Lumber	10'-0"	15
W2	2x4 Wall Plate, short	12'-0"	6
W3	2x4 Wall Plate, long	18'-0"	6
W3.1	2x4 Bevel Plate	18'-0"	1
W4	Door Header	8'-0"	2
W5	Door Trimmer	8'-0"	2
W7	4ft. x 8ft. Textured Plywood Siding, See exterior materials		
ROOF FRAMING MATERIALS			
CODE	DESCRIPTION	LENGTH / SIZE	QTY.
R1	2x8 Rafter	14'-0"	12
R2	O.S.B. roof sheeting	4'x8'x 7/16"	10
R4	2x8 Fascia	20'-0"	2
R12	2x8 Blocking	18'-0"	2
R15	Simpson H2.5 Hurricane Tie		16
DOORS			
D1	See door plans for materials or purchase pre-hung doors		
	6068 Pre-Hung Door, per owner	6'-0" x 6'-8"	1
	Verify jamb size and rough opening for pre hung doors		
FASTENERS (see door plans for door fasteners)			
2 1/2"	8d Coated Sinker-Roof Sheet, Joist/Rafter to Wall		10 lbs
3 1/4"	12d Coated Sinker-Floor Joist, Wall Frame		8 lbs.
2 1/2"	8d Galvanized-Siding		10 lbs.
	Metal Roof 1/4" hex head screw with neoprene bonded washer		4 lbs.
	Optional Asphalt Roof 1 1/4" long, 12 gauge, 3/8" head Roofing Nail		5 lbs.
	Optional Trim Screws #9 flat head, polymer 2.5"		
	Construction Adhesive	10 oz.	5